

Second National Bank Building
12 Office Street
Bel Air
private

This 1900 Beaux Arts building is perhaps the best architect designed building in Town. The work of Bel Air's favorite, George Archer, the building shows both his skill and Bel Air's preference for chaste design. The upward thrust of the massive central arch is increased by the rusticated quoins and pilasters, but this soaring thrust is firmly earthbound by the horizontals of the modillioned cornice and the parapet. The reverse downward thrust of the windows and oculi makes a firmly balanced facade, the most stylish in Bel Air and reminiscent of some of the Ernest Flagg buildings under construction at the Naval Academy in the same years.

The building was built for the Second National Bank of Bel Air which had its office at 30 Office Street at the time. In 1934 its assets were sold to the newly established First National Bank of Bel Air by Robert Archer, the receiver of the Second National Bank.

In 1966 the bank acquired the building next door to the west from Mrs. Charles Reed. This building had been built by David Wilson after 1881. The old building was remodeled by Gerard A. Baxter, a Bel Air architect, and merged with the Beaux Arts building to make a happy and coherent whole which preserves the pleasant human scale of the Courthouse Square.

MARYLAND HISTORICAL TRUST

HA-1462
1314624612

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

Second National Bank Building

AND/OR COMMON

First National Bank Building

2 LOCATION

STREET & NUMBER

12 Office Street

1st

CITY, TOWN

Bel Air

— VICINITY OF

CONGRESSIONAL DISTRICT

STATE

Maryland

COUNTY

Harford

3 CLASSIFICATION

CATEGORY

☐ DISTRICT

☒ BUILDING(S)

☐ STRUCTURE

☐ SITE

☐ OBJECT

OWNERSHIP

☐ PUBLIC

☒ PRIVATE

☐ BOTH

PUBLIC ACQUISITION

☐ IN PROCESS

☐ BEING CONSIDERED

STATUS

☒ OCCUPIED

☐ UNOCCUPIED

☐ WORK IN PROGRESS

ACCESSIBLE

☒ YES: RESTRICTED

☐ YES: UNRESTRICTED

☐ NO

PRESENT USE

☐ AGRICULTURE

☒ COMMERCIAL

☐ EDUCATIONAL

☐ ENTERTAINMENT

☐ GOVERNMENT

☐ INDUSTRIAL

☐ MILITARY

☐ MUSEUM

☐ PARK

☐ PRIVATE RESIDENCE

☐ RELIGIOUS

☐ SCIENTIFIC

☐ TRANSPORTATION

☐ OTHER:

4 OWNER OF PROPERTY

NAME

First National Bank of Maryland

Telephone #: 244-4000

STREET & NUMBER

25 S. Charles Street

CITY, TOWN

Baltimore

— VICINITY OF

STATE, zip code

Maryland 21201

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,

REGISTRY OF DEEDS, ETC.

Harford County Court House

STREET & NUMBER

Main Street

CITY, TOWN

Bel Air

STATE

Maryland 21014

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

☐ FEDERAL ☐ STATE ☐ COUNTY ☐ LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

CONDITION
☒ EXCELLENT ☐ DETERIORATED
☐ GOOD ☐ RUINS
☐ FAIR ☐ UNEXPOSED

CHECK ONE
☐ UNALTERED
☒ ALTERED

CHECK ONE
☒ ORIGINAL SITE
☐ MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The present First National Bank building is located on the north side of Office Street in the Town of Bel Air, Harford County, Maryland. It is composed of two buildings, to the east the former Second National Bank building and to the west the former Reed building. The buildings were merged in 1966 by Gerard A. Baxter, Inc., a firm of Bel Air architects.

The old bank building is a two story, flat-roofed, stone rubble building with a smooth stone facade in a restrained Beaux-Arts style reminiscent of some of the simpler Ernest Flagg buildings which were built at the same time at the Naval Academy. The facade is divided into three bays by the strong vertical lines of the rusticated quoins and two similar pilaster strips, all decorated at the top with cartouches. The center bay is entirely occupied by the two story entrance arch. The entry is recent, but the three windows in the top of the arch are original. The flanking bays each have a clean-set 1/1 double-hung window in the first story and a deeply-set oval bulls-eye window with a stone frame decorated with raised keystone shapes at the cardinal points in the second story. The vertical movement of the facade is balanced by the strong horizontals of an architrave and a dentil-banded cornice topped by a parapet with projecting panels over the quoins and pilaster strips. The building's east elevation shows signs of having been raised (see detail picture). About half-way up the northeast corner brick quoins begin and the quality of the stone work appears different. Perhaps the building was originally only 1-1/2 stories tall.

The Reed building, acquired by the bank in 1966, is a two story brick structure with a hipped roof. Originally the entrance was to the east and had long window lights and a three-paned transom. A similarly designed window was to the west. The second story windows were 1/1 double-hung, set in wooden frames. When Baxter incorporated the two buildings, he removed the entrance and window in the first story and replaced them with two pairs of double-hung 6/6 windows. The three second story windows became 6/6 and acquired louvered shutters. The corbelled accent strip between the first and second stories remains. The original inside end chimney in the west elevation was removed at the time of the renovation.

Along the western side where the two buildings are joined one may observe the sensitive marriage of these two disparate styles. Baxter chose to build a glass wall parallel to the west bank wall starting about half-way in the rear elevation of the Reed building. This added space is used as a hall and contains a staircase to the second stories of both buildings. He left the rough stone of the bank's west wall exposed, thus providing a pleasing contrast of textures - smooth glass, rough stone, and semi-smooth brick. To tie the Reed building to the bank in a visual way he had it painted a light beige color which resembles the stone of the larger building.

A series of alterations radically changed the interior space of both buildings. The banking room has had its ceiling dropped and has lost its marble wainscot and the old counters. The Reed building was gutted upstairs and down and an entry was knocked in its east wall to provide

9 MAJOR BIBLIOGRAPHICAL REFERENCES

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

The Second National Bank Bldg. occupies parcel #824 and the Reed Bldg. occupies parcel #825 in the Town of Bel Air.

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE _____ COUNTY _____

STATE _____ COUNTY _____

11 FORM PREPARED BY

NAME / TITLE

M. Larew

4 January 1979

ORGANIZATION

Town of Bel Air

STREET & NUMBER

39 Hickory Avenue

CITY OR TOWN

Bel Air

TELEPHONE

838-8700

STATE

Maryland 21014

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

for circulation. Bank offices now occupy this building and the second story of the bank. With the exception of a few steps down from the banking room into the Reed building there is no interior indication that the buildings were ever separate and none that the interiors were not designed yesterday.

Outside along the west side a small landscaped green space separates the bank from its next door neighbor, the County Office Building at 18 Office Street.

The original bank building is an unusually suave design for Bel Air and the combination of the two buildings maintains the pleasant human scale of the structures around the court house.

TITLE
FIRST NATIONAL BANK BUILDING
SECOND NATIONAL BANK BUILDING

Owner: First National Bank of Maryland

first building:

1972 First National Bank of Maryland merged
 with First National Bank of Bel Air
 Banking House

- 234/402 22 May 1934
 Robert H. Archer, receiver of Second National
 Bank (equity docket 1/48)
 to
 First National Bank of Bel Air
 \$22,500, lot, bldg., fixtures
- 99/233 20 March 1900
 Lucie B. Bailey & Shirley, husband, of Kennebec
 Maine
 to
 Second National Bank of Bel Air
 \$1500
 (Second National Bank had been at 30 Office St.)
- 94/278 27 September 1898
 Georgie Jacobs et al
 to
 Lucie Bailey

This land comes from the estate of Thomas Hays.
 It was devised to his daughter, Pamela Hays, and,
 failing her issue, to his daughter, Elizabeth
 Jacobs. A court case (1876) forced the land to
 sale for the benefit of Elizabeth and her children.
 The grantors in 94/278, as well as the grantee, are
 Elizabeth's children.

second building:

- 717/233 15 July 1966
 Annie L. W. Reed, widow
 to
 First National Bank, Harford County
- 242/277 13 October 1936
 H. Elizabeth Esley, unmarried
 to
 Charles H. Reed & Annie, w.

242/276 same day Reeds to Esley -

203/475 4 August 1927
Safe Deposit & Trust Co., of Baltimore (surviving
executor of David J. Wilson)
 to
Charles H. Reed
\$6100

42/334 28 February 1881
Stevenson Archer, Trustee in Jacobs vs. Jacobs
(equity 36/33 1876)
 to
David Wilson
the land was part of that left by Thomas Hays
to his daughter Pamela. Failing issue of
Pamela, the income was to pass to another
daughter, Elizabeth Jacobs and her children.
This suit was to force sale of the land and
investment of the proceeds.

MARYLAND HISTORICAL TRUST
21 STATE CIRCLE
SHAW HOUSE
ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
Individual Structure Survey Form

COUNTY: Harford	SURVEY NUMBER: HA-1462
TOWN: Bel Air	NEGATIVE FILE NUMBER:
LOCATION: 12 Office Street Bel Air, Md. 21014	UTM REFERENCES: Zone/Easting/Northing
COMMON NAME: First National Bank Bldg.	U.S.G.S. QUAD. MAP:
FUNCTIONAL TYPE: Commercial	PRESENT FORMAL NAME: First National Bank Bldg.
OWNER: First National Bank of Md. ADDRESS: 25 S. Charles St. Baltimore, Md. 21201	ORIGINAL FORMAL NAME: Second National Bank Bldg.
ACCESSIBILITY TO PUBLIC: Yes (X) No () Restricted ()	PRESENT USE: Bank
LEVEL OF SIGNIFICANCE: Local (X) State () National ()	ORIGINAL USE: Bank
GENERAL DESCRIPTION: Bank Bldg = 1 Reed Bldg. = 2 Structural System	ARCHITECT/ ENGINEER : George Archer (Bank Bldg.)
1. Foundation: Stone(1)Brick(2)Concrete()Concrete Block()	ENGINEER /CONTRACTOR: D. J. Shanahan (Bank Bldg.)
2. Wall Structure	PHYSICAL CONDITION OF STRUCTURE: Excellent (X) Good () Fair () Poor ()
A. Wood Frame: Post and Beam()Balloon()	THEME: Architecture
B. Wood Bearing Masonry: Brick(2)Stone(1)Concrete()Concrete Block()	STYLE: Beaux-arts/Vernacular
C. Iron() D. Steel() E. Other:	DATE BUILT: 1900/c. 1881
3. Wall Covering: Clapboard()Board and Batten()Wood Shingle()Shiplap() Novelty()Stucco()Sheet Metal()Aluminum()Asphalt Shingle() Brick Veneer()Stone Veneer() Bonding Pattern: Other:	
4. Roof Structure	
A. Truss: Wood()Iron()Steel()Concrete()	
B. Other:	
5. Roof Covering: Slate()Wood Shingle()Asphalt Shingle()Sheet Metal() Built Up()Rolled()Tile()Other:	
6. Engineering Structure:	
7. Other:	
Appendages: Porches()Towers()Cupolas()Dormers()Chimneys()Sheds()Ells() Wings ()Other:	
Roof Style: Gable()Hip(2)Shed()Flat(1)Mansard()Gambrel()Jerkinhead() Saw Tooth()With Monitor()With Bellcast()With Parapet()With False Front() Other:	
Number of Stories: 2	
Number of Bays: 6	Entrance Location: Office St.
Approximate Dimensions: 55' x 64'	
THREAT TO STRUCTURE: No Threat (X) Zoning() Roads() Development() Deterioration() Alteration () Other:	LOCAL ATTITUDES: Positive (X) Negative() Mixed() Other:

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

Interior completely remodeled c. 1966 at the time the Reed Bldg. was added to the Bank Bldg.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

The Bank Building is an elegant and sophisticated structure. The combination with the Reed Bldg. was well done and is a good example of the successful blending of two styles into an attractive & coherent whole.

REFERENCES:

MAP: (Indicate North In Circle)



FNB
Bldg.
12

Office St.

Courthouse

Main St.

SURROUNDING ENVIRONMENT:

Open Lane() Woodland() Scattered Buildings()
Moderately Built Up() Densely Built Up()
Residential() Commercial(X)
Agricultural() Industrial()
Roadside Strip Development()
Other:

M. Larew


RECORDED BY:

Town of Bel Air

ORGANIZATION:

16 October 1978

DATE RECORDED:




hatched


MARILYNN LAREN

FIRST NATIONAL BANK
12 OFFICE ST
BEL AIR, MARYLAND

HA-1462

SCALE - 3" = 32'





DRAWN: MARILYNN LAREW

TRACED: G. CUNO

FIRST NATIONAL BANK
12 OFFICE STREET
BEL AIR, MARYLAND

HA-1462

SCALE: 3 in = 32 ft





REED BLDG, PART OF FIRST NATIONAL BANK BLDG
12 OFFICE ST. BEL AIR

SOUTH & WEST ELEVATIONS

M. LAREW, 1976

HA-1462



FIRST NATIONAL BANK

1st
First National Bank
OF KANSAS CITY, MO.

FIRST
NATIONAL
BANK
DEPT. FOR S.
SAVINGS
SALE DEPOSIT
BUILD FOR FUTURE





Second National Bank Bldg.
detail of stone work in east
elevation

M. Larew 1978

HA-1462



First National Bank Bldg.
detail of glass wall joining rear of Reed Bldg.
M. Larue 1978

HA-1462



Second National Bank + Reed Bldg Looking North
(1st Nat'l Bank Bldg)

Office St.

8-10-78

M. Larew

HA-1462



Reed Bldg. as renovated 1966, s. + w. elevations
M. Larue, 1978

HA - 1462



Second National Bank Bldg.

detail of stone work, windows &
Parapet

Photo: M. Larew 1978

HA - 1462

FIRST NATIONAL BANK

1ST
First National Bank

AT THE
BANK
SALES

HA-1462



HA-1462



HA-1462





HA-1462



Reed Building c. 1960
Office St.
Bel Air

HA-1462

THIS PHOTOGRAPH
By: W. Robert Wallis
Fountain Green Road
Bel Air, Md.